

Instrument #: 2018-2046
 12/26/2018 11:09:39 AM Total Pages: 1
 SCC SECTION CORNER CERTIFICATES
 Recording Fee: \$ 7.00
 Shirley Troyna, Recorder, Chickasaw County Iowa



Prepared by: Erdman Engineering, P.C., 708 Commerce Drive, P.O. Box 246, Decorah, Iowa, (563)382-4194

UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE
 OF

Land Survey Monuments situated in Section 19, Township 95 North, Range 13 West, of the Fifth Principal Meridian, Chickasaw County, Iowa, Previously recorded in does not apply in the County Recorder's Office.

Monument Description and Remarks:


This certificate is prepared in accordance with Section 365.11 of the Code of Iowa. No previous certificates have been filed for these corner locations.

SSE 1/8 Corner: We found no record of the SSE 1/8 Corner being set. We found no evidence of a monument in the field other than the county road and a fence line running south. We found the S 1/4 Corner and the SE Corner. We set a 1/2" diameter steel bar with 1 1/2" aluminum cap #11442 on line and midway between the S 1/4 Corner and the SE Corner as the SSE 1/8 Corner of Section 19, Township 95 North, Range 13 West.


PLAN-VIEW
 (NOT TO SCALE)

SSE 1/8 CORNER

Set 1/2" diameter steel bar with 1 1/2" aluminum cap #11442



SECTION 19



Cor A,
 19-95-13

I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of Iowa.

Lindsay Erdman 12/14/18
 Date

Lindsay Erdman, P.E. & P.L.S.
 Licensed Professional Land Surveyor
 Iowa License Number 11442
 My License renewal date is December 31, 2018
 Pages or sheets covered by this seal: THIS SHEET ONLY

List Corner(s) to be Indexed

Corner(s)	Section	Township	Range
SSE 1/8	19	95N	13W



ERDMAN
ENGINEERING, P.C.
 CIVIL ENGINEERING & LAND SURVEYING
 Decorah, Iowa